

PART 1 - GENERAL

- 1.1 Related Documents
- A. Conditions of the Contract, and the Supplements thereto by City of Bellingham apply to the work specified in this Section.
- 1.2 Work Area
- A. The Contractor shall confine operations and storage to the designated work and storage/staging areas. Keep all areas and adjacent surfaces clean and orderly.
- 1.3 Required City of Bellingham Permits
- A. A City business license must be obtained by the Contractor prior to the City issuing any permits.
 - B. The Contractor will be required to pay for the City business license.
 - C. The Contractor shall make applications and pay for all required permits (e.g. Stormwater, Grading, etc.) from the City of Bellingham prior to starting construction of the associated improvements.
- 1.4 Emergency Service
- A. The Contractor shall designate and shall provide the Owner and the Landscape Architect with names and telephone numbers of those persons who will be available at all times in case of emergency. The Contractor will be charged for such expenses as may be incurred by the Owner to provide such service, if said emergency is not immediately rectified.
- 1.5 Temporary Facilities
- A. The Contractor shall provide all temporary facilities required to execute work in a safe, workmanlike manner.
- 1.6 Electrical Power
- A. Contractor to provide all electrical power as required for Construction. Costs related to providing electrical power are incidental to this project.
- 1.7 Telephone
- A. Contractor shall provide a mobile phone with back-up answering service to insure communication access during normal working hours.
- 1.8 Water
- A. Water is not available on site.
- 1.9 Toilet
- A. Contractor shall provide his/her own restroom facilities.
- 1.10 Dust & Dirt Control (See Sheet C4 and Section 02374)
- A. The water placement includes that required for dust control while site grading excavating for the installation of the structures and appurtenances for processing and compacting the subgrade, for dust control between the time of subgrade preparation for the restoration, seeding, pavement repair and crushed surfacing.
 - B. Dust control water shall be applied as designated by the Owner, and for such period of time as he deems necessary.

- C. Contractor shall ensure that dust and debris resulting from construction activities are removed from local streets.
 - D. The cost of water placement shall be incidental to the base bid.
 - E. The contractor shall obtain a water hydrant use permit from the City of Bellingham at his/her expense.
 - F. Provide dust and dirt control. Sprinkle as required to quell dust. Protect occupants, neighboring property, passers-by and visitors from injury or discomfort from dust. Protect in accordance with requirements of Air Pollution Control Authority and local and State standards.
- 1.11 Guards & Barricades
- A. The Contractor shall provide temporary barricades, safety guards and warning lights at all open excavations and other unsafe areas outside of the fenced work area. Barricades shall physically prohibit passage of pedestrians into excavations and protect the health, safety and welfare of the public.
- 1.12 Noise
- A. Perform construction work during standard 7am to 5pm, Monday through Friday business hours per City of Bellingham Supplements to the APWA Standard Specifications. Contractor requests to work other than standard hours including a description of work must be submitted in writing and approved by the Owner twenty-four hours prior to the alternate start of work.
- 1.13 Traffic Control
- A. If at any time the Contractor's activities result in closure, substandard condition, restrictions to traffic use of all or portions of the roadway which are specified to remain open to traffic, the Contractor shall immediately, at his own expense, furnish all material, labor, equipment, necessary to restore the streets to the satisfaction of the Engineer. Work necessary to restore the streets to traffic shall continue on a round-the-clock basis until they are reopened to traffic in conformance with the specifications. Upon failure of the Contractor to immediately provide the necessary material, labor, equipment, to restore the streets to traffic when ordered to do so by the Engineer, the City shall be at liberty without further notice to the Contractor or his Surety, to provide the necessary material, labor and equipment to restore the streets to traffic and to deduct all costs thereof from any moneys or payments due or to become due the Contractor.
 - B. All costs of traffic control shall be incidental to the project.
- 1.14 Cleaning During Construction
- A. Cleaning for Specific Products
 - 1. See Specification Section for that work.
 - B. Safety Requirements
 - 1. Maintain project in accordance with applicable safety and insurance standards. Conduct cleaning and disposal operations to comply with local ordinances and anti-pollution laws.
 - 2. Store volatile wastes in covered metal containers, and remove from premises daily. Prevent accumulation of wastes that create hazardous conditions. Provide adequate ventilation during use of volatile or noxious substances.
 - 3. Do not burn or bury rubbish and waste materials on project site. Burning of timber slash will be permitted only as approved by City of Bellingham Fire

Department and State Agencies. Do not dispose of volatile wastes such as mineral spirits, oil, or paint thinner in storm or sanitary drains.

C. Materials

1. Use only cleaning materials recommended by manufacturer of surface to be cleaned. Use cleaning materials only on surfaces recommended by cleaning material manufacturer.

D. Cleaning During Construction

1. Execute cleaning to ensure that neighboring grounds, and public properties are maintained free from accumulations of waste materials and rubbish. Wet down dry materials and rubbish to lay dust and prevent blowing dust.
2. Each day during progress of work, clean site and public properties and dispose of waste materials, debris and rubbish. Provide on-site dump containers for collection of waste materials, debris and rubbish. Remove waste materials, debris and rubbish from site and legally dispose of at public or private dumping areas.
3. Where the Contractor, subcontractors, and/or suppliers are using Local street for hauling debris, disposal material, imported material, equipment, or other purposes, special care shall be exercised to prevent spillage or scattering of debris, materials, liquids, dirt rock, mud and/or other foreign matter upon the street right -of -way. Should spillage or scattering occur and be deemed as dangerous to public safety by the Owner, the Contractor shall clean the spillage or scattering immediately. If the spillage or scatterings are not cleaned up within a reasonable time, the Owner shall order the work done by others and the costs are to be paid by the Contractor.

E. Final Cleaning, See Section 01700.

1.15 Temporary Field Offices & Sheds

B. Not required.